HL-CYB-001

Acceptance criteria and approval gates

Enterprise Zero Trust Security Architecture

Document version f0e5f8af1e2c

Acceptance answers two different questions: did the engineer verify the approved work, and did the owner accept it for its intended use? Keep those decisions separate. Repository/documentation checks have evidence in the task reports; lab implementation is PLANNED and its operational controls are NOT TESTED.

The criteria below define what evidence a reviewer needs. A passing continuous integration (CI) run checks the repository; owner user acceptance testing (UAT) needs explicit confirmation. See the glossary for these terms.

1. Task 001 bootstrap criteria

Table 1. Task 001 bootstrap criteria

ID	Criterion	Verification
B01	Preserve existing work, inspect tooling/authentication/target repository, and resolve conflicts before mutation	Preflight report and Git/remote inspection
B02	Create every requested file/directory with useful content or a clearly scoped future-use README	Required-structure validator and Git tree
B03	Assignment covers scenario, business case, measurable requirements, scope, dependencies, architecture, threats, standards, deliverables, tests, 100-point rubric, publication, and honest achievement objectives	Validator anchors/rubric plus independent content review
B04	Guide covers A-L with prerequisites, procedures, proposed commands, expected outcome, verification, rollback, and completion criteria for every stage	Stage-section validator plus manual feasibility review
B05	Architecture protects home/production, defaults deny, addresses management/egress/DNS/IPv6/secrets/logging, and flags unverified hardware/resources	Cross-document review; no operational test claim
B06	AGENTS.md contains stage approval, documentation-first, bounded work, production/destructive restrictions, public hygiene, verification/UAT separation, tracking, and controlled Git workflow	Governance review
ID	**Criterion**	**Verification**
B07	All local Markdown destinations/anchors resolve; required IDs are traceable;	Local checks and hosted CI

ID	Criterion	Verification
	focused validator tests and whitespace checks pass	
B08	Proposed published contents and history contain no detected secrets, actual internal addresses, sensitive exports, or proprietary source, and receive manual public-safety review	T00/T17; acknowledge pattern-scan limits
B09	Authorized public GitHub repository uses `main`; official checkout action is commit-pinned, token is read-only, credentials are not persisted, and documentation-only CI passes	GitHub metadata and actual Actions run
B10	`origin` is correct, local `main` tracks remote `main`, status is clean, and local/remote SHA match; report URL/user/branch/SHA/CI/blockers	Required Git synchronization commands and remote read-back
B11	No software install, VM creation, infrastructure/network/identity change, or security-test execution occurred; stop after Task 001	Executed-action review and explicit completion report
B12	Open decisions/risks and one recommended next task are reported; owner UAT is not inferred	Final report; owner review remains pending
B13	Every completed task has a unique sequential finalized A-H report in `reports/`; historical finalized reports are preserved	Reporting validator, source comparison, Git history review
B14	Maintained user-facing documents outside `reports/` have faithful searchable PDF editions; task reports/addenda require Markdown only; final project report remains a template	Document source/PDF manifest and fresh rebuild, report exclusion/archive regression checks, text/navigation/page checks, representative visual QA, and CI

If GitHub authentication/permissions block publication, B09/B10 remain blocked and the local reviewed repository plus precise owner action are delivered. Do not present a local-only repository as published. If the target already exists, preserve and reconcile its branches/content without force-pushing.

2. Future stage acceptance

Obtain scope-specific owner approval **before each stage**. To finish a stage, record engineering checks, reviewed evidence, unresolved issues, and the owner's separate acceptance decision. Finishing one stage does not authorize the next.

Table 2. Future stage acceptance

Stage	Minimum exit evidence	Blocking condition
A	Verified hardware/disk ownership, usable capacity, offline cable plan, backup/console feasibility, and go/no-go	Uncertain asset ownership or unverified destructive-install target
B	Supported isolated hypervisor, administrator/MFA, console recovery, patch/capacity record	Missing disk approval/backup or unmanaged protected-network connection
C	Six zone bridges, no ordinary guest uplink/host routing, reviewed IPv6 and console rollback	Shared physical/home bridge or unaccounted forwarding
D	Effective default-deny policy, management protection, scoped allows, mocked boundary verification	Broad LAN allow, protected path, exposed administration, unapproved egress
E	Separate lab forest/DNS/GPO, synthetic identities, recovery/evaluation deadlines	Production trust/sync/credentials or broken domain dependencies
F	Supported Windows/Linux endpoints, host firewall, standard/admin separation	Dual-homed guest, real corporate profile, or ordinary-user admin access
G	Offline root, separate issuer, scoped templates, valid/untrusted/revoked relying-application results	Exported CA key, broad enrollment, production trust, or unsupported revocation claim
H	Twelve role/resource cases, same-zone enforcement, measured revocation	Any unintended resource/admin access or unmet revocation target
I	Two separate sequential lab pilots, narrow resources, MFA/recovery, deny/revocation and route/DNS evidence	Corporate enrollment, wildcard access, subnet/exit exposure, or unresolved safe egress
J	Six sources, at least 19/20 timely events, clock target, retention design/health evidence	Missing source class, unsupported claimed export/encryption, or unbounded disk growth
K	Executed traceable cases, all critical passed, noncritical threshold met, no high-severity issue	Unexecuted mandatory cases, hidden failure, or unapproved test scope
L	Two bounded automations, repeat-run verification, encrypted off-compute timed restore, final evidence/report, owner UAT	Unproven recovery, unsupported claims, secret publication, or pending final owner acceptance

An owner-approved scope exception must record affected requirements/tests, justification, risk, revised acceptance, and rubric impact before evaluation. Unavailable features remain a gap until that decision; do not silently lower targets.

3. Engineering verification record

In the individual task report, identify the stage/branch, approval/date, actual versions and asset roles, changed files/configuration, requirement/test IDs, expected and actual results, evidence IDs, verifier and second observation, defects/severity, rollback readiness, and verdict. Mark missing tests NOT TESTED. A second tool or observation supports verification; it is not a second human reviewer unless someone else participated.

4. Owner UAT record

Record the owner/reviewer, date, business workflows checked, observed usability, accepted limits, follow-up items, and explicit acceptance decision separately. Leave owner UAT pending until the owner supplies that decision. Engineering completion, GitHub publication, and CI do not supply owner acceptance.

5. Current gate

Task 001 technical results are recorded in T1-Report.md, its separately recorded addenda, and the final chat completion response. Every future task must finalize its own individual report before engineering completion. FINAL-REPORT.md remains the project-level template. Owner UAT: **PENDING**. Stages A-L: **NOT STARTED / NOT APPROVED FOR EXECUTION**. No next task starts without the owner's scope-specific authorization.