Lab Implementation Guide

How to use the guide

The analyst reads reports. The engineer reads maintenance instructions. The unassigned user is denied. Follow the assignment for required outcomes.

Follow the five phases in order: infrastructure, identity and endpoints, access controls, monitoring and recovery, then validation and submission. Read each procedure first. Obtain approval before each stage A-L, covering assets, changes, validation and rollback. Use the architecture and technical reference for detail.

Use private copies of the five Office files, numbered **01-05**. Record observations, dates and private evidence references in the named sections. Use synthetic users and separate lab passwords; keep raw evidence private. Leave unperformed checks **NOT TESTED**. If a result differs, stop the affected work, follow its recovery plan and log it in **Deliverable 04 > Issue Log**.

Phase 1: Prepared Infrastructure

Verify the Dell Precision 5820 with Proxmox, HP desktop with physical OPNsense, TP-Link TL-SG108E switch and GL.iNet Beryl AX upstream router.

Before you start: Have read-only stage A approval, the private network map and backup/recovery record, and Dell/HP console access. Missing map, version or recovery details mean stop. Changes need separate B (host), C (network) or D (firewall) approval; this phase installs nothing.

A. Verify the lab equipment and VM resources

WHERE

Dedicated lab administrator computer; Dell and HP consoles. Use private management addresses.

STEPS

1. Sign in at both consoles. Compare device identities and cables with the private map. Confirm the original Windows disk, data and services remain protected and their recovery record is available.
2. Open **Proxmox > Dell node > Summary**, then storage > **Summary**. Compare CPU, memory and usable storage with the capacity budget and reserves.
3. Select **DC1**, **WIN1** and **APP1 > Hardware** in turn. Compare processors, memory and disk allocations with that budget. Physical OPNsense on HP is outside these guest totals.
4. Compare the GUI inventory with device labels and the private physical/firmware record. Record a difference before continuing.

CHECK	Exactly three workload VMs; allocations total 6 vCPU / 16 GiB RAM / 160 GiB disks. Measured capacity also covers host, free-space and temporary-restore reserves. Both consoles and recovery records are available.

RECORD	**Deliverable 01 > Hardware & Readiness**, **Virtual Machines** and **Resource Allocation**. Enter observations and evidence references.

B. Verify network zones and management access

WHERE

Administrator computer: Proxmox, HP OPNsense and switch web pages.

STEPS

1. Open **OPNsense > Interfaces > Assignments**. Match Management, Corporate and Restricted to the HP ports and private map.
2. Open **Proxmox > Dell node > System > Network**. Compare bridge ports, addresses and VLAN-aware settings with the approved relationships.
3. Open each VM's **Hardware > Network Device**. Match bridge and VLAN tag to the map: DC1/WIN1 in Corporate; APP1 in Restricted, with one zone NIC each.
4. Open the switch's **VLAN > 802.1Q VLAN** and **802.1Q PVID Setting** pages. Compare tagged/untagged membership and port defaults with the map; change nothing.
5. Inspect the management restrictions: named administrator sources/services, effective host/device rules, supported multifactor authentication and console recovery.

> **CHECK** Three zones reach HP; no switch/host route bypasses OPNsense. Workload bridges have no host address. Only the dedicated path reaches management; APP1's approved overlay is the sole extra interface.

> **RECORD** **Deliverable 01 > Network Zones** and **Allowed Network Flows**.

C. Verify isolation and required network access

WHERE

Administrator computer: read-only Windows, Beryl AX and firewall/host views.

STEPS

1. Open Windows **Settings > Network & internet > Advanced network settings**. Compare adapters with the isolation record; flag extra Wi-Fi, VPN or shared connections.
2. In Beryl AX **INTERNET**, inspect **Ethernet**, **Repeater**, **Tethering** and **Cellular**. Keep upstream disconnected until independent isolation and egress are approved.
3. Compare FF-01 through FF-08 with effective firewall/host rules, states, NAT and listeners. Use the flow checklist; unlisted access stays denied.
4. Complete the IPv4/IPv6, route and trust checks. GUI inspection alone does not prove home/production isolation.
5. For separately approved active validation, use lab-owned mocks. Record allowed and denied behavior plus policy/log evidence under FWT-01/FWT-02. Never probe home or production.

> **CHECK** Map/flows match. FWR-01/FWR-02 need FWT-01/FWT-02 evidence and second observations. Unperformed active checks stay **NOT TESTED**.

> **RECORD** **Deliverable 01 > Allowed Network Flows** and **Deliverable 03 > Test Cases**.

Before Phase 2: Resolve mismatches; carry pending checks forward. For unexpected connectivity, stop and use console isolation/recovery.

Phase 2: Identity and Endpoint Security

DC1 manages lab Windows accounts; WIN1 uses them; APP1 has a protected Linux baseline. Coverage: FWR-03/FWR-04 and FWT-03/FWT-04.

Before you start: Approvals: E for directory work, F for endpoint settings; missing workload creation also needs the applicable host/network approval. Have the private identity/network plan, approved media, versions, policy values and console recovery. Keep lab DNS, time, credentials and identities separate from home/production; create no trust or identity synchronization.

A. Verify or create the three workload VMs

WHERE

Proxmox > Dell node, then each guest's **Hardware** and **Console**.

STEPS

1. Find **DC1**, **WIN1**, **APP1**. Verify existing guests; create a missing guest only with approval and the guest profiles. Protect the original Windows disk/services.
2. Check CPU / RAM / disk: **DC1 2 / 6 GiB / 64 GiB; WIN1 2 / 6 GiB / 64 GiB; APP1 2 / 4 GiB / 32 GiB**; retain host/recovery reserves.
3. In **Hardware > Network Device**, match the private bridge/tag/MAC map: one zone NIC each; Corporate for DC1/WIN1, Restricted for APP1. Management stays separate; physical OPNsense is on HP.
4. Open **Console**. Verify name, supported OS/build, approved media, private recovery and lawful offline update/activation. Windows 11 needs supported CPU, UEFI/Secure Boot and TPM 2.0; no bypass.

CHECK	Three workload VMs; own virtual disks; totals 6 vCPU / 16 GiB / 160 GiB. Resolve a mismatch through approved console recovery.
RECORD	**Deliverable 01 > Virtual Machines / Resource Allocation**; **02 > Implementation Overview**. Include update/activation gaps.

B. Configure DC1 and Active Directory

WHERE

DC1 console, approved administrator: **Server Manager**. Active Directory (AD) manages Windows users.

STEPS

1. Open **Local Server > Ethernet > adapter Properties > Internet Protocol Version 4 > Properties**. Set approved Corporate address/mask/gateway and **DC1 as DNS**, without external alternates. Check name/MAC/time.
2. Verify an existing directory; otherwise use **Manage > Add Roles and Features > Role-based or feature-based installation > DC1 > Active Directory Domain Services**. Include tools; install.
3. For a new forest only: notification flag > **Promote this server to a domain controller > Add a new forest**. Enter **ad.lab.test**, retain DNS and approved functional levels; store the DSRM recovery credential privately.
4. Review prerequisites and paths, resolve warnings, install and restart.
5. Open **Tools > DNS > DC1 > Forward Lookup Zones > ad.lab.test**. Check host/service records and forest/controller health, including SYSVOL/NETLOGON.

CHECK	Forest/controller/DNS work. Role installation alone is insufficient. On failure inspect DNS/time/prerequisites; use supported directory recovery.
RECORD	**Deliverable 02 > Active Directory and User Roles**; **03 > Test Cases**, FWT-03.01-.03.

C. Create lab users and groups, then join WIN1

WHERE

DC1 **Server Manager > Tools > Active Directory Users and Computers**; WIN1 console.

STEPS

1. In **ad.lab.test**, verify or create the approved organizational units (OUs) or containers for users, groups, privileged identities and member computers. Keep DC1 in **Domain Controllers**; do not assume **Users** is the approved folder.
2. In the user folder select **New > User**. Create missing **ava**, **eli**, **uma**, with unique private passwords and approved first-logon choices. Verify the separate named administrator in its privileged folder.
3. Select **New > Group** in the group folder: **Global**, **Security**. Create/verify **LabReaders**, **LabMaintainers**, **LabAdmins**. In **Properties > Members > Add**, use **Check Names**: Readers = ava/eli; Maintainers = eli; Admins = separate administrator only.
4. Inspect each user's **Member Of** and each group's **Members**. Keep uma outside both application-related groups and all three standard users outside privileged groups. Assign only approved administrator rights; group names grant none.
5. Open DC1 **Tools > DNS > Forward Lookup Zones > ad.lab.test > New Host (A or AAAA)**. Add/verify **app**, IPv4 A record, with APP1's approved private address.
6. On WIN1 set its approved Corporate address/gateway and DC1-only DNS. Open **System Properties > Computer Name > Change > Domain**, enter **ad.lab.test**, use the prompted join credential and restart. Move WIN1 to the approved computer OU on DC1.
7. Sign in on WIN1 as **ava@ad.lab.test**. Verify lab DNS, domain membership and policy using the join checks. Test eli/uma logon within approval.

CHECK	Three standard users, three role groups and one separate privileged administrator; memberships and standard logon agree. AD groups do not assign Apache roles. On failure, inspect DNS/time/membership and correct only the approved object; never elevate a standard user.
RECORD	**Deliverable 02 > Active Directory and User Roles**; **03 > Test Cases**, FWT-03.01-.03. Later application roles use distinct passwords; six access cases and revocation remain required.

D. Apply Windows security policies

WHERE

DC1 **Server Manager > Tools > Group Policy Management**; DC1/WIN1 security consoles.

STEPS

1. Link the account-policy Group Policy Object (GPO) at **Domains > ad.lab.test**. Enter approved password/lockout values.
2. Link WIN1's endpoint GPO to its computer OU: Microsoft Defender enabled; all Windows firewall profiles **On**, inbound **Block**; reviewed exceptions only.
3. Apply WIN1 logon auditing and a separate DC1 GPO at **Domain Controllers**, using the exact auditing paths.
4. In **Windows Defender Firewall with Advanced Security > Inbound Rules**, scope AD/DNS/time rules. Remove approved broad overlaps; FF-02 needs same-zone host enforcement.
5. Inspect winning policy, protection and updates on both targets. Check WIN1 **Administrators**; run the standard-user denial/admin control.

CHECK	Settings and privileges match approval; policy/log evidence supports behavior. On failure restore changed pilot settings at console; keep protections enabled.

RECORD	**Deliverable 02 > Windows and Linux Endpoint Controls**; **03 > Test Cases**, FWT-03/FWT-04.

E. Configure APP1 networking and host protection

WHERE

APP1 Proxmox **Console**, approved sudo administrator. APP1 stays outside AD.

STEPS

1. Match interface MAC with **Hardware > Network Device** and the private map. Inspect addresses/routes/DNS/rules; save recovery copies.
2. If needed, edit Netplan: approved private interface/address/gateway, DC1-only DNS. Check syntax, use the timed trial and verify rollback.
3. Verify lab-only time, without public/corporate DNS/time fallback or another backend.
4. Apply nftables policy: default-deny input/forward, exact WIN1/admin HTTPS, IPv4/IPv6 restrictions; future overlay on APP1 alone.
5. Use initial load or scoped atomic replacement. Preserve other tables. Verify rules/routes/services/reboot persistence; test HTTPS permit/deny when its listener exists.

CHECK	Configuration/state agree; forwarding is off. On failure restore saved files at console. Never flush all rules or add another firewall manager.

RECORD	**Deliverable 02 > Windows and Linux Endpoint Controls**; **03 > Test Cases**, FWT-04. Include second observations.

Before Phase 3: Compare directory/logon/DNS/policy/privilege evidence. Unperformed FWT-03/FWT-04 checks, including later app cases, stay **NOT TESTED**. Resolve failures through approved console recovery; directory rebuild/snapshot rollback needs separate supported recovery approval.

Phase 3: Zero Trust Access Controls

Let approved users reach the right HTTPS page, then prove that removed permissions stop working. Coverage: FWR-03/05/06 and FWT-03/FWT-05/FWT-06.

Before you start: Approvals: G for certificates/trust, H for Apache, I for remote access; E also covers AD revocation. Have private versions/network/identity records, saved configurations and console recovery. External access needs independently isolated, approved egress. Use the linked references; missing scope means stop.

A. Create and verify HTTPS certificates

WHERE Approved existing offline signing workstation: terminal; APP1 Proxmox **Console**; WIN1 lab browser.

STEPS

1. On the offline signer, create the encrypted CA key and 365-day public root in a new private directory. Keep the key offline and passphrase in recovery custody; add no CA VM/service.
2. On APP1 create its private server key and certificate signing request. Transfer only the request to the signer.
3. On the signer, sign one 90-day leaf for **app.ad.lab.test**. Verify subject alternative name (SAN), serverAuth, chain/constraints, dates and remaining validity; leave domain time unchanged.
4. Transfer public certificates to APP1; keep its key root-only. After B starts HTTPS, record WIN1's untrusted rejection, then import only the fingerprint-checked public root into its approved lab store and retry. Never bypass warnings.

CHECK	Correct chain/name/dates; untrusted rejection then normal trusted HTTPS. No home/production trust changes. On failure stop and use certificate recovery.
RECORD	**Deliverable 02 > HTTPS Certificate Configuration**; **03 > Test Cases**, FWT-05: public properties, custody/scope, browser evidence. **02 > Implementation Results and Limitations**: certificate-revocation services excluded.

B. Configure the Apache application and accounts

WHERE APP1 Proxmox **Console**, approved sudo administrator and root editor; WIN1 browser.

STEPS

1. Save settings. Use approved Apache 2.4/password-utility packages/media; create synthetic pages at **/reports/** and **/maintenance/**.
2. Create/verify separate test accounts **ava**, **eli**, **uma**, with distinct application passwords. Create the password file once; never overwrite it to add a user.
3. Set manually assigned roles in **/etc/labapp/groups**: **LabReaders: ava eli**; **LabMaintainers: eli**; uma neither. AD provides Windows logon: no application single sign-on or automatic synchronization, no fourth app administrator.
4. Apply HTTPS/group configuration; require each page's group. Disable HTTP/reviewed default sites; syntax-check before restarting.
5. Verify Apache active, **TCP 443 only**, protected key/password/group files, no extra service. Complete A's trust sequence; preserve FF-03 firewall/host restrictions.

CHECK	HTTPS/group checks work. On failure inspect DNS/TLS/files and restore saved settings. Never use a generic authenticated-user allow.
RECORD	**Deliverable 02 > Application Accounts and Permissions**; **03 > Test Cases**, FWT-03.10/FWT-05: versions, effective files, roles and evidence. Exclude passwords/hashes.

C. Test the six application access cases

WHERE WIN1 **Browser > Developer tools > Network**; APP1 console: Apache logs.

STEPS

1. Use a fresh browser context per user and valid application credentials. Close all private windows between users.
2. Disable cache; reload each exact path. Confirm the actual server request/status using the evidence method.
3. Compare all six requests with Apache logs/effective groups; keep eli's working maintenance context for D.

Case	Account	Page	Expected HTTP result
C01	ava	/reports/	ALLOW / 200
C02	ava	/maintenance/	DENY / authenticated 403
C03	eli	/reports/	ALLOW / 200
C04	eli	/maintenance/	ALLOW / 200
C05	uma	/reports/	DENY / authenticated 403
C06	uma	/maintenance/	DENY / authenticated 403

CHECK A failed login/401 or unreachable service is not role denial. On failure preserve evidence; inspect account/group/inherited rules.

RECORD **Deliverable 03 > Test Cases**, FWT-03.04-.09; link from **02 > Six Application Access Tests**. FWT-03.01-.03 and mapping/revocation .10-.13 remain mandatory.

D. Revoke an application permission

WHERE APP1 root editor; DC1 **AD Users and Computers**; WIN1 browser.

STEPS

1. Confirm eli's maintenance access; save groups and change time against a separate observer clock.
2. In **/etc/labapp/groups**, remove eli from **LabMaintainers**, keeping **LabReaders: ava eli** and ownership/mode.
3. Under E approval remove eli on DC1: approved **LabMaintainers > Properties > Members**. Record both changes; AD membership does not update Apache.
4. Disable cache; force a **/maintenance/** server request in eli's existing authenticated browser, then a fresh context with valid app credentials. Compare both with Apache logs/effective groups; check reader access.

CHECK Both maintenance requests return authenticated 403; reader permission stays. On failure inspect files/cache/inheritance. Restore permissions only with recorded explicit test/recovery approval.

RECORD **Deliverable 03 > Test Cases**, FWT-03.10-.13; **02 > Access Revocation**. Record changes, request/denial times, observed elapsed time and cache/state treatment; no revocation-time SLA.

E. Configure, test and revoke Tailscale access

WHERE Separate lab **Tailscale admin console > Access controls / Machines**; APP1 console; one approved existing Windows remote client.

STEPS

1. Verify independent isolation, identities, MFA and recovery before external egress. The client must have no direct zone route to APP1. Missing prerequisites leave FWT-06 **NOT TESTED**.
2. Save the lab policy; apply the explicit deny-all baseline before enrollment. Inspect every additive grant/ACL, SSH rule and tag owner; a blank policy is insufficient.
3. Enroll APP1 and the existing client with separate approved lab identities. Inspect device records. Keep subnet routes, exit node, Tailscale SSH, Funnel, Serve and public sharing off; use no home/production identity or trust.
4. Apply the exact client-to-APP1 TCP 443 grant; review enrolled addresses privately. Map app.ad.lab.test to APP1's overlay address, approve only lab-root trust, and verify independent APP1 host rules/forwarding. FF-06 adds no DC1, WIN1, Proxmox or OPNsense access.
5. Test approved HTTPS, unauthorized identity and wrong listening port/resource. Use working positive controls and vendor/device/host/Apache evidence. A closed port or broken DNS is insufficient. The Phase 5 mock dependency needs separate scope; do not broaden grants.
6. Restore the approved context through its authorized sequence; confirm working HTTPS. Record time, then remove the client grant and exact device authorization, keeping APP1 intact.
7. Force new server requests in the existing browser and a fresh context. Both must fail; compare policy/device/log state, observed denial time and cache/connection-state treatment. Re-enrollment or permission restoration needs approval.

CHECK	Only approved APP1 HTTPS works; unauthorized/wrong-port and both revoked contexts deny. OPNsense alone cannot prove overlay enforcement. On failure stop remote access and use deny-all/device recovery.
RECORD	**Deliverable 03 > Test Cases**, every FWT-06 subcheck; **02 > Tailscale Remote Access / Access Revocation**. Include evidence, actual elapsed time and final device/policy state; keep identities/addresses/raw logs private.

Before Phase 4: Compare all mandatory FWT-03/FWT-05/FWT-06 subchecks with second observations; missing work stays **NOT TESTED**. Log failures in **04 > Issue Log**. Recover saved app/policy files, lab-only trust and exact remote authorization within approval; preserve key custody and failed evidence.

Phase 4: Monitoring, Automation and Recovery

Outcome: five explainable events, one denied-access investigation, one safely repeated capacity script and one isolated APP1 restore. Approvals: J and the explicit L automation/recovery portions. Tests: FWT-07/FWT-08/FWT-09; requirements: FWR-07/FWR-08/FWR-09. Use existing local logs; no collector, security-monitoring product or extra permanent VM is needed.

Step 20 - Open the logs and produce five benign events

Purpose and location: under J approval, view DC1 Security, OPNsense firewall and Apache access/error logs. These are three sources; Apache access/error files are one application source. Record source/observer UTC (Coordinated Universal Time), time differences, restricted access and rotation in **03 / Security Events** before comparing events.

1. On DC1 open **Event Viewer > Windows Logs > Security > Filter Current Log**. Select the relevant time range and event IDs **4768,4771**, after confirming Step 11's Kerberos success/failure auditing. These directory events are generated on the domain controller; a WIN1 interactive logon event is not automatically a DC1 event. Microsoft documents 4768 ticket requests and 4771 pre-authentication failures.
2. In OPNsense open **Firewall > Log Files > Live View**, filter the named lab interface/source/destination/service and confirm the intended deny rule is logged. Check current states if a repeated request produces no new rule match.
3. On APP1 read only the needed log interval using the following commands. Restrict exports to the approved log reader and keep originals private. Review **/etc/logrotate.d/apache2** and Windows log maximum-size/retention properties against the measured disk budget; change only approved values, without clearing logs.

READ-ONLY - APP1 console, sudo/root or approved log-reader access. Show the last 40 application records from the selected Ubuntu site paths. No replacements; output may contain private addresses/usernames:

```
sudo tail -n 40 /var/log/apache2/labapp-access.log
sudo tail -n 40 /var/log/apache2/labapp-error.log
```

Check: a request appears with the expected path/status/user/time and a denied request has its corresponding authorization context. If files are missing, inspect the active site's ErrorLog/CustomLog and Apache permissions; do not assume an empty view means no event occurred.

4. Produce the following categories once within the approved action/rate. Reuse an existing recorded app case or deny when its evidence meets the requirement; do not generate duplicate traffic just to fill a sheet.

Event	Approved action	Source and expected observation
E01 directory success	On connected WIN1, sign out/in as an existing standard lab user with valid credentials	DC1 Security: successful Kerberos request attributable to that online logon
E02 directory failure	Verify the selected synthetic account is not near lockout; make one deliberately wrong-password logon attempt, then stop	DC1 Security: the relevant failure, often 4771; no repeated guesses

Event	Approved action	Source and expected observation
E03 app allow	Request ava /reports/ with valid app credentials	Apache: authenticated allowed request, normally 200
E04 app denial	Request ava /maintenance/ with valid app credentials	Apache: authenticated role denial, normally 403
E05 firewall denial	Make Step 24's one approved request to a known listening lab-only mock through the intended deny	OPNsense: matching blocked flow/rule; a disconnected listener is insufficient

5. For each category record actual source/action, source UTC, observer UTC, time difference, concise event summary and private evidence reference in **03 / Security Events**. If using only two sources, obtain the approved selection that still makes all five categories observable. Do not count five identical web requests as five categories.

READ-ONLY - APP1 local Linux console, approved log-reader; elevate only if journal access requires it. Optional service troubleshooting shows system-journal entries since local midnight, without a pager; no placeholders:

```
journalctl --since today --no-pager
```

Check: match its timezone/service messages to the action; Apache requests remain in the separate files above. If permission/time filters hide entries, resolve the view before generating another event. systemd's journal reference explains these filters.

If it fails: check auditing, actual online rather than cached logon, time range/timezone, site log path, rule logging and rotation. Do not repeat failed passwords or disable lockout to manufacture a record. Preserve the missing-evidence result as NOT TESTED until resolved.

Step 21 - Explain one denied-access event

Purpose and location: in **03 / Denied Access Investigation**, explain an observed denial using the existing event, effective policy and a working allowed control. This is one investigation, not a new attack exercise.

1. Choose E04 or E05 and refer to its **Security Events** ID. Record who requested what, the machine/client context, time and actual visible outcome.
2. Check the intended control: for E04 compare authenticated app username, resource and group membership; for E05 compare source/destination/service and the exact OPNsense rule. Record the observed reason rather than guessing from the word denied.
3. Link a known working allowed control to the same service: for example eli's approved maintenance access before revocation, or the administrator's allowed mock connection. Confirm the target was listening when the denied request occurred.
4. Compare the log's time/status/rule with the browser/request observation and effective file/policy. Explain why a bad password, broken DNS or stopped service is not the intended authorization/segmentation result.
5. Record conclusion, second observation, evidence ID and any defect reference. Add an actual problem to **04 / Issue Log** if correction is needed; preserve the original failure and later retest.

Check: another reader can follow request, intended policy, observed deny and supporting control without seeing credentials or raw logs. Link FWT-07 in **03 / Test Cases**; do not claim broader detection or enterprise log-retention performance.

If it fails: keep the conclusion unverified and obtain the missing source/policy observation. Do not change an allow into a deny expectation after seeing the result.

Step 22 - Run the one capacity-summary automation

Purpose and location: under L automation approval, use local Windows PowerShell on **WIN1** as a standard user with access to the approved private output directory. The operation reads local disk capacity and replaces one JSON summary; it does not alter accounts, networking or system configuration.

1. Review the exact script below, its target allowlist and output location before saving it privately. Use an existing reviewed directory outside every Git checkout; inspect its permissions and ensure neither directory nor output is a junction/symlink pointing elsewhere. The path check below is not a substitute for this review.
2. Save the script in the approved private script file. Leave the WIN1/ad.lab.test checks unchanged in the real operation. Use the existing PowerShell policy/signing path; do not add an execution-policy bypass.

CONFIGURATION CHANGE - WIN1, local Windows PowerShell, standard user with approved write permission. This proposed script queries local fixed disks and writes only WIN1-capacity.json. OutputDirectory is the one required runtime path, not a credential:

```
param([Parameter(Mandatory)][string]$OutputDirectory)
$system = Get-CimInstance -ClassName Win32_ComputerSystem
if ($system.Name -ne 'WIN1' -or $system.Domain -ne 'ad.lab.test') {
    throw 'Target is outside the approved lab operation.'
}
$directory = Get-Item -LiteralPath $OutputDirectory -ErrorAction Stop
if (-not $directory.PSIsContainer) { throw 'Output must be a directory.' }
$cursor = $directory
while ($null -ne $cursor) {
    if (Test-Path -LiteralPath (Join-Path $cursor.FullName '.git')) {
        throw 'Keep the capacity record outside Git.'
    }
    $cursor = $cursor.Parent
}
$capacity = Get-CimInstance -ClassName Win32_LogicalDisk -Filter 'DriveType=3' |
    Select-Object DeviceID, Size, FreeSpace
$capacity | ConvertTo-Json |
    Set-Content -LiteralPath (Join-Path $directory.FullName 'WIN1-capacity.json')
-Encoding utf8
```

Check before running: expected target/domain and one private replacement file match the approval. If a path/target is uncertain, stop without running it.

3. Set **$LabCapacityScriptPath** and **$LabCapacityOutputDirectory** privately to the reviewed script file and output directory. Invoke it as follows; the call changes only the named summary.

CONFIGURATION CHANGE - WIN1, same standard-user PowerShell and approved paths. Run the reviewed local operation. Both variables must be assigned to approved absolute paths first; never use a remote target:

```
& $LabCapacityScriptPath -OutputDirectory $LabCapacityOutputDirectory
```

Check: WIN1-capacity.json contains **DeviceID**, **Size** and **FreeSpace**, in bytes. Compare each drive with **File Explorer > This PC > drive Properties**. Use the displayed byte counts or convert consistently; GiB means 1,073,741,824 bytes. A successful script exit alone is insufficient.

4. Run the same reviewed script a second time. Compare files changed and the current disk/settings views: only the intended summary is replaced; free space can change naturally. Record the observation in **03 / Automation Verification**, A01-A07, and reference FWT-08 in **Test Cases**.
5. For safe invalid-target testing, make a disposable private copy of the script and change only its expected hostname literal to an intentionally nonexistent lab name. Run that copy on WIN1 with the same reviewed output directory; expect the target error **before any output write**. Verify the existing summary is unchanged. Do not rename WIN1, change its domain or contact another computer. Preserve the reviewed real script unchanged.
6. For invalid-path testing, use the real script with an approved known nonexistent directory or an existing ordinary file as OutputDirectory. Expect the Get-Item/directory error and no new/replaced summary. Inspect the intended output separately after each rejection; remove the disposable test copy only under approved cleanup.

If it fails: stop and compare target/domain, write rights, literal path, units and script error. Do not elevate or widen paths to force success. Remove only the intended output if recovery permits; preserve failure evidence and the original script.

Step 23 - Back up APP1 and restore it in isolation

Purpose and location: under L recovery approval, use Proxmox Backup/Restore and an already approved encrypted external storage target. Restore one temporary APP1 copy while preserving the original and the only backup. A snapshot or ordinary Proxmox archive alone is not encrypted off-compute backup.

Before starting: the encryption/mount/transport backend is still an owner decision. L approval must identify the exact external device, its existing encryption, recovery-key custody, supported mount/unmount steps, storage capacity, unused temporary VM ID, cleanup and rollback. No disk formatting or new encryption product/server is prescribed here. If this prerequisite is missing, FWT-09 is NOT TESTED.

Before choosing the final backup state, decide under the existing E/H/I approval scope whether the lab should remain revoked or return to its normal analyst/engineer/remote workflows. For normal handover, restore eli to **both** AD/application LabMaintainers, and separately re-enroll/re-authorize only the exact approved remote client with the narrow grant. Record the changes, new device/address if applicable and affected permit/deny retests before backing up. If restoration is not approved, retain the revoked state and report the unavailable workflow as a limitation; do not claim normal engineer/remote acceptance.

1. On APP1 record the private backup manifest: synthetic pages under **/srv/labapp**, the active Apache configuration, **/etc/labapp** including hashed users/groups, server key/leaf and public root, and required guest networking/firewall/time settings. In the conditional Ubuntu profile use the commands below before shutdown. Do not copy keys/password hashes or the private manifest into public evidence.

CONFIGURATION CHANGE to one private manifest, otherwise READ-ONLY - original APP1 console, root shell, L approval. Inspect the named manifest path before creation; preserve any older record. The selected profile must have all listed paths. Hash declared files without printing their content:

```
sudo -i
umask 077
LabManifestPath=/root/APP1-manifest.sha256
find /srv/labapp /etc/apache2 /etc/labapp /etc/netplan /etc/nftables.conf
/etc/systemd/timesyncd.conf.d -type f -exec sha256sum -- {} + > "$LabManifestPath"
```

Check: no path/read errors, every declared file has a manifest entry and no file content was printed. Copy this private original manifest through the approved media path to separate protected custody before backup; it is the comparison reference, not a public artifact. If a path differs/missing, correct the approved scope/profile instead of silently excluding it.

2. At the Proxmox console verify the approved external encrypted volume is actually mounted and unlocked using its approved backend procedure. Inspect the exact device/mount and available space; an empty directory on the host's own disk is not the backup target. Verify the separate recovery key can unlock the volume under the approved check. Keep that key separate from the stored backup.
3. In **Datacenter > Storage**, select the reviewed existing backup storage. For the conditional new **Directory** entry use **Add > Directory**, **ID: lab-backup** only if that unused ID is approved, **Directory: the exact mounted encrypted external path**, **Content: VZDump backup file**, and the intended node only. Require a mounted target with the guard below; do not allow fallback writes to the host directory. The directory-storage manual explains the backend; encryption comes from the approved underlying volume, not a Backup now checkbox.

CONFIGURATION CHANGE followed by READ-ONLY - Proxmox console, root, approved lab-backup Directory entry only. Set LabBackupMountPath privately to that entry's exact external mount path first. The option marks storage offline when its mount is absent; it does not mount, format or encrypt a device. Verify syntax against the selected pvesm reference:

```
pvesm set lab-backup --is_mountpoint 1
findmnt --mountpoint "$LabBackupMountPath"
lsblk -o NAME,TYPE,FSTYPE,MOUNTPOINTS
pvesm status
```

Check: the exact path is a mounted external device, **lab-backup** is active with sufficient space and its storage configuration shows the guard. Compare the device/encryption chain and unlock/recovery result to the approved backend record; a filesystem label or active storage alone does not prove encryption. Missing/wrong mount or unverified encryption means stop before backup.

4. Cleanly shut down APP1 through its guest console and confirm **Stopped**. Keep it off for the drill. Select **APP1 > Backup > Backup now**, the verified encrypted external storage, **Mode: Stop**, and the approved compression. Review the selected VM/storage, then start. In the task log confirm successful completion and inspect archive identity, date, size and included disk(s). Record backup time/age and manifest in **03 / Backup & Restore**, B01-B03.

5. In the storage's **Backups** view select that exact APP1 archive > **Restore**. Enter the approved unused temporary ID and reviewed guest-disk storage. Keep **Start after restore/live restore** off; review the original ID is not selected. Start the independent observer clock **immediately before confirming Restore**. Restore without overwriting the original or sole archive. Proxmox's backup/restore manual governs selected-version details.
6. Before starting the copy, open its **Hardware > Network Device > Edit > Advanced > Disconnect** for every NIC. Set **Options > Start at boot: No**. Confirm original APP1 is still off. Start only the copy via **Console** and keep it disconnected.

CONFIGURATION CHANGE - restored APP1 copy's console only, sudo/root, L approval. Stop and disable the copied overlay service before any client attachment. Do not run this on the original APP1. Conditional Ubuntu/systemd profile; no placeholders:

```
sudo systemctl disable --now tailscaled
sudo systemctl is-active tailscaled
```

Check: the copied service is inactive; the second command normally exits nonzero for inactive. Inspect the copy's NIC-disconnected state independently in Proxmox. If service identity/state is unclear, leave the copy disconnected and stop the drill.

Before changing the copy's firewall for testing, transfer the separately retained private original manifest to its approved comparison path and check restored integrity:

READ-ONLY - restored APP1 copy console, root for protected files. Set LabOriginalManifestPath privately to the approved original manifest file, then compare all declared files. No file is modified:

```
sha256sum -c "$LabOriginalManifestPath"
```

Check: every declared file reports **OK** before temporary test changes. If a file is missing/mismatched, preserve that result and investigate the archive/scope; do not rewrite the manifest to match the restore.

7. Use the approved existing Restricted bridge for the temporary recovery test **only after disconnecting every other path**: original APP1 stays off; disconnect OPNsense's vmbr20 NIC; attach the one existing WIN1 test NIC to vmbr20 with a temporary unused Restricted address, no gateway, and a private hosts entry for app.ad.lab.test. Preserve WIN1's previous adapter/hosts/bridge settings first. Confirm no physical port, host address or other route exists on vmbr20. Do not create a fourth permanent zone or attach the copy to Management/home.
8. While still disconnected, save the restored copy's original firewall file. On that **copy only**, use Step 12's scoped replacement transaction to add **ip saddr LAB_RESTORE_CLIENT_IP tcp dport 443 counter accept**, substituting the approved temporary WIN1 address. Put it after the existing physical-source HTTPS permit and before the input chain's closing brace; retain the earlier tailscale0 drop and final drop policy. Record this intentional post-integrity-check difference.
9. Attach only the copy's single NIC to isolated vmbr20 and enable its link. Confirm no live duplicate or Tailscale service. Reuse WIN1's approved lab root trust and map app.ad.lab.test privately to the restored address. Restore/remove the temporary permit during cleanup; do not broaden the source subnet.

10. Stop the independent observer clock when the declared integrity/service checks establish usable application recovery. Open HTTPS and test **ava /reports/** allow and **ava /maintenance/** authenticated deny, which hold in both approved eli membership states. Include this functional verification in actual elapsed time. Syntax checks alone do not establish recovery. Record time, integrity and behavior in **03 / Backup & Restore**, B04-B10, and FWT-09 in **Test Cases**.
11. Shut down/disconnect the copy after review. Under approved cleanup restore WIN1's saved NIC/address/hosts settings and the firewall NIC attachment, verify the copy cannot start/connect automatically, then resume original APP1 only after the isolation check. Verify original HTTPS/roles and overlay state through their approved path. Keep the sole backup safe; any copy deletion needs the exact cleanup scope.
12. Safely unmount/lock and detach the external encrypted backup through the approved backend procedure and store it away from the compute host. Record readable recovery custody, backup age, measured recovery and exclusions. This drill does not test AD, CA or Proxmox disaster recovery and promises no enterprise recovery-time target.

Check: a real backup/restore task, independent clock, manifest comparison and restored HTTPS/role behavior agree. The final off-compute copy is encrypted, with separate recovery access. No original disk, original APP1, sole backup or duplicate overlay identity was overwritten/connected.

If it fails: keep original and backup safe, leave the copy disconnected, record the failure and inspect encryption access, archive/disk coverage, storage space, network/firewall and service state. Do not reconnect broadly, retry against the original ID or erase the only archive.

Phase 4 checkpoint and recovery

FWT-07 requires five categories plus one explained denial; FWT-08 requires actual output, safe repeat and target/path rejection; FWT-09 requires an actual isolated restore with data/HTTPS/role evidence. Record only observed results. Recovery preserves source logs and backups, changes only approved settings/output, and leaves the recovery copy disconnected until exact cleanup is approved.

Phase 5: Validation and Final Submission

Outcome: ten fully evidenced engineering results, five clear submissions and a separate owner acceptance decision. Approvals: K validation and remaining L closeout. Test: FWT-10; requirement: FWR-10. Earlier observations can be reused only while they describe the current configuration and meet every mandatory check.

Step 24 - Prepare the permitted and denied network checks

Purpose and location: under the exact D/H/I/K validation scope, use existing lab guests and listeners to distinguish a real deny from a broken service. These are subchecks of FWT-01/FWT-02/FWT-06, not extra exercises or permanent resources. Freeze source, target, identity, single destination port, expected result, observer, stop condition and cleanup before each check.

1. Establish a working allowed control: WIN1 opens APP1 HTTPS and the dedicated administrator opens the lab management interfaces. Compare the active listener to the relevant permit/policy. If the control fails, diagnose it before the negative test.

2. For FWT-01's protected-boundary mock, use **APP1's lab address**, never a real protected address. Under the approved temporary rule scope, add a separate **MOCK_PROTECTED** alias containing that lab address and a logged Corporate rule blocking **WIN1 > MOCK_PROTECTED > TCP 443**, ahead of FF-03. Keep real protected networks physically absent. Make the one frozen request, compare its denial with this exact rule/counter, remove only the temporary mock rule/alias, and confirm normal FF-03 access again. The real isolation conclusion also requires cable/routes/trust review; the mock is one behavioral observation.
3. For FWT-02 unlisted inter-zone access, use DC1 as the source to the known listening APP1 TCP 443 while only WIN1 has FF-03 permission. For ordinary-user management denial, use WIN1 to Proxmox TCP 8006 with the dedicated-admin control working. Compare the intended network/host deny, not just a failed password prompt.
4. For FWT-06's wrong listening port, temporarily configure Apache's existing APP1 service to listen on one approved unused mock port such as **8443**. This example is conditional on that exact port/scope approval. Save the site/ports files, add the following separate temporary file in the approved Ubuntu Apache configuration directory, enable it, syntax-check and reload as in Step 16. No new page, account or software is needed.

CONFIGURATION CHANGE - APP1 root editor, temporary /etc/apache2/conf-available/lab-mock.conf; approved 8443 mock only. Configuration content, not commands; reuse the synthetic document tree and deny page content. The positive control needs only a listening TCP connection:

```
Listen 8443
<VirtualHost *:8443>
    ServerName app.ad.lab.test
    DocumentRoot "/srv/labapp"
    <Directory "/srv/labapp">
        Require all denied
    </Directory>
</VirtualHost>
```

Check before enabling: the port is unused, the exact temporary listener has approval, and no new Tailscale grant or ordinary-user permit is added.

CONFIGURATION CHANGE followed by READ-ONLY - APP1 console, sudo/root, temporary mock scope. Enable only that named configuration and verify syntax/listening. No placeholders once 8443 is approved:

```
sudo a2enconf lab-mock
sudo apachectl configtest
sudo systemctl reload apache2
sudo ss -lntp
```

Check: proceed to reload only after Syntax OK. Confirm Apache listens on 8443; if parsing fails, disable the named mock configuration and restore the saved files before reloading.

5. Use Step 12's console-only replacement transaction to add **ip saddr LAB_ADMIN_IP tcp dport 8443 counter accept** after the physical-source HTTPS permit and before the input chain's closing brace; retain the tailscale0 drop and final drop policy. Replace the source with the exact dedicated administrator IPv4 address. OPNsense's corresponding temporary FF-05 Management permit must name the same source/destination/port. Keep the vendor TCP-443-only grant unchanged. Confirm the administrator reaches the listener, then make the frozen remote wrong-port request; it must be denied. Match the actual vendor/host rule state/counter; do not claim one layer caused the deny without evidence.

6. After the recorded check, disable only **lab-mock** with the Ubuntu **a2disconf lab-mock** service helper, syntax-check, reload and confirm 8443 is no longer listening. Remove the exact temporary host/firewall permits through the saved transaction. Recheck production/home isolation and normal APP1 HTTPS. Preserve the temporary-rule evidence privately; add no permanent fifth VM or fourth zone.

READ-ONLY bounded connection check - approved Windows lab source, local PowerShell, standard user. Set **$LabApprovedTarget** privately to the one approved lab-owned address/name and **$LabApprovedPort** to its single frozen port. This makes a TCP connection attempt only; it is not a scan or a protected-network probe:

```
$connection = [System.Net.Sockets.TcpClient]::new()
try {
    $attempt = $connection.ConnectAsync($LabApprovedTarget, $LabApprovedPort)
    if (-not $attempt.Wait(5000)) { throw 'Lab connection timed out.' }
    'TCP CONNECTED'
} catch {
    'NO TCP CONNECTION: ' + $_.Exception.Message
} finally {
    $connection.Dispose()
}
```

Check: the positive control prints TCP CONNECTED; a denied attempt prints NO TCP CONNECTION and has matching intended policy/log/counter evidence. A timeout alone remains inconclusive. Do not supply a home/production address, loop through ports or rerun repeatedly to force a result.

If it fails: preserve the observation, restore only the named temporary configuration under the approved plan and recheck normal access. Missing approval or working listener means NOT TESTED, not permission to broaden access.

Step 25 - Execute and record the ten tests

Purpose and location: in **03-Security-Monitoring-and-Testing.xlsx / Test Cases**, turn observed behavior into an accurate engineering record. The workbook already contains the approved methods and mandatory child checks; do not create another result template in this guide.

1. Open **Test Cases**, enable the existing table's filter and select a **Test ID**. Read its **OVERALL** row and every numbered child row, along with the authoritative Test Plan. Freeze actual source/target/user/version, approval/date, action/rate, stop/rollback and evidence ID in the linked private record.
2. Perform the approved action, compare the outcome with the expected result and obtain the separate observation described below. Enter actual result, evidence, operator/date/version and defect/retest references in the existing columns. Never enter a planned outcome as an actual result.

Test / requirement	What to do and compare
FWT-01 / FWR-01	Steps 1-6/24: compare physical/firmware inventory to readiness records; inspect cables, bridges, other adapters, routes/IPv6, trust/data/credential isolation and disconnected or approved independent egress; prove the listening mock deny with its matching policy evidence.

Test / requirement	What to do and compare
FWT-02 / FWR-02	Count one host/four VMs/three zones and compare measured capacity/reserves. Verify FF-01-FF-08, named admin/MFA limits, console recovery, HTTPS permit, unlisted/ordinary-user management denial and same-zone host rules against actual sessions/logs.
FWT-03 / FWR-03	Steps 8-10/15-17: inspect directory/DNS/policy/counts and standard logon; run C01-C06 with valid app credentials. Compare app file/log decisions, then prove removed eli maintenance permission denies existing/fresh requests and record actual timing.
FWT-04 / FWR-04	Steps 11-12: inspect supported builds, updates, antivirus, applied policy, host firewalls, rights, single NICs/APP1 overlay exception, listeners/forwarding. Compare a harmless standard-user admin denial with the approved admin control.
FWT-05 / FWR-05	Steps 13-16: inspect encrypted offline CA custody and leaf chain/SAN/serverAuth/constraints/dates/remaining validity. Compare the normal trusted browser session with the otherwise working client's pre-import rejection. No warning bypass or domain-time change.
FWT-06 / FWR-06	Steps 18-19/24: inspect separate tailnet/MFA/recovery/device identity, narrow additive policy, no routes/shares/SSH/Funnel/Serve and effective host/DNS rules. Demonstrate approved HTTPS, unauthorized identity, wrong listening-port/resource and existing/new revoked access, with actual times/state treatment.
FWT-07 / FWR-07	Steps 20-21: match all five event categories to real actions, source/observer times and separate policy/group observations; inspect access/rotation and explain the one denial. Keep private source records.
FWT-08 / FWR-08	Step 22: review target/private-path guard, run the one operation, compare output with OS storage, repeat and check target/path rejection. Compare before/after state; only the intended summary may change.
FWT-09 / FWR-09	Step 23: inspect encrypted off-compute backup scope/key access/time/manifest, original-off/disconnected-copy state and inactive copied overlay. Compare restore output to independent time, hashes/content and actual isolated HTTPS allow/deny; state exclusions.
FWT-10 / FWR-10	Steps 25-27: check every requirement/mandatory result/evidence/defect, five files and unchanged rubric; complete sensitive-data/publication review and engineering cutoff/verifier. Verify actual publication through the linked governance workflow and keep owner UAT separate.

3. Mark **PASS** only when the actual result and all mandatory evidence/second observations match. Mark an observed mismatch **FAIL**. Mark an unexecuted, blocked or unverified mandatory check **NOT TESTED**. A mandatory test cannot be waived with NOT APPLICABLE.
4. Set the OVERALL row to PASS only after every mandatory child passes. Preserve failures and use **04 / Issue Log** for correction/retest. Do not change an expected deny into an allow or silently replace the original evidence.
5. In **03 / Requirements Coverage**, connect all ten FWR rows to the final test/evidence/defect references. Use **Evidence Index** for private-original references and separately reviewed public artifacts; raw paths/addresses never become public links.

Check: the ten OVERALL rows and every mandatory child have an accurate verdict and traceable evidence. A second observation can be another log/UI/policy view; it is not independent human

sign-off. Any missing mandatory evidence blocks engineering completion, and a critical safety failure blocks acceptance regardless of score.

If it fails: leave the affected result FAIL or NOT TESTED, explain the issue and obtain bounded remediation/retest approval. Continue only work whose dependencies remain safe; do not erase the failed attempt.

Step 26 - Finish the five Office deliverables

Purpose and location: in the private working copies of the five released templates, assemble the existing records into a clear submission. Keep detailed test execution in 03 and cross-reference it elsewhere.

1. **01-Lab-Environment-and-Architecture.xlsx:** finish **Hardware & Readiness**, **Virtual Machines**, **Network Zones**, **Allowed Network Flows** and **Resource Allocation**. Replace planned assumptions with observed fields only after verification, preserve procurement versus installation status and reference the private topology/public sanitized diagram appropriately.
2. **02-Identity-and-Zero-Trust-Implementation.docx:** complete **Implementation Overview**, **Active Directory and User Roles**, **Windows and Linux Endpoint Controls**, **Application Accounts and Permissions**, **HTTPS Certificate Configuration**, **Six Application Access Tests**, **Tailscale Remote Access**, **Access Revocation**, and **Implementation Results and Limitations**. Summarize configuration and link execution evidence in 03; do not paste password files/keys.
3. **03-Security-Monitoring-and-Testing.xlsx:** complete **Security Events**, **Denied Access Investigation**, **Test Cases**, **Requirements Coverage**, **Automation Verification**, **Backup & Restore**, and **Evidence Index**. Leave **Owner Acceptance** PENDING until explicit owner confirmation; test PASS does not fill that decision.
4. **04-Troubleshooting-and-Lessons.xlsx / Issue Log:** record actual problems, impact/cause, approved correction, verification/retest and practical lesson. Preserve unresolved items and original failure references; do not invent a troubleshooting story.
5. **05-Final-Project-Submission.docx:** complete **Executive Summary**, **Project Objectives**, **Architecture Overview**, **Implementation Summary**, **Security Testing Results**, **Key Findings**, **Challenges and Lessons Learned**, **Project Limitations**, **Final Evaluation**, and **Supporting Deliverables and Evidence**. Explain what works and what remains blocked, citing the owning records instead of copying their tables.
6. In **05 / Final Evaluation**, apply only the assignment's existing 100-point rubric: 25 infrastructure/network, 25 identity/access, 20 monitoring/operations, 20 testing/recovery and 10 documentation/submission. Record actual evaluator/date, engineering verifier and evidence cutoff. Unsupported plans earn no implementation credit.

Check: exact filenames and worksheet/section names match the blank templates, all claims point to observed evidence, limits are visible and raw private records remain outside Git. The separate project-level final report remains a template until its own real evidence/reporting is authorized.

If it fails: fix the editable working record and trace its claim to current evidence. A blank template, screenshot placeholder or total score cannot replace a mandatory test or owner acceptance.

Step 27 - Review evidence, submit and obtain owner acceptance

Purpose and location: at the approved publication workstation under L closeout scope, release only reviewed public-safe work and ask the owner to assess the intended workflows. Follow the engineering publication/build instructions and repository workflow; internal automation/branch mechanics belong there.

1. Review the whole proposed submission, not only the changed paragraph: filenames, document properties, hidden sheets/comments, screenshots, links and proposed Git history. Keep tokens/passwords, keys, hashes of passwords, actual addresses, private inventory, corporate details, raw logs/captures, backups and filled private working files outside the public set. Publish only explicitly reviewed sanitized summaries/artifacts. An ignore rule does not remove previously tracked content.
2. Capture evidence narrowly: show the relevant action/result and sanitized rule/group context. Keep source timestamps and private originals intact; review a separate redacted copy, including metadata. Do not alter the original to make a result look successful. Record reviewer/date and redaction/limitations in **03 / Evidence Index**.
3. Complete the linked documentation/report, Office-preservation, link, PDF/rebuild and focused checks for the proposed publication. Inspect the changed PDFs visually. Resolve findings and verify actual PR/CI/merge and local/remote synchronization using the established workflow; record only observed outcomes in the existing evidence record. Documentation checks do not validate lab controls.
4. Give the owner the five reviewed files and evidence index. In **03 / Owner Acceptance**, have the owner assess analyst report access, engineer maintenance access, unassigned/revoked denial, remote behavior and understandable recovery/evidence records. Record usability observations, limits/follow-ups, reviewer/date and explicit confirmation reference.
5. Keep engineering verdicts, rubric scoring and owner UAT distinct. UAT remains **PENDING** until that confirmation is supplied. Stop at the authorized boundary; do not begin another stage or project task from a publication result.

Check: the public set contains only reviewed safe material, FWT-10 has its actual required evidence, and owner acceptance accurately records the owner's decision. No CI result, score or second tool observation supplies that decision.

If it fails: stop publication on a sensitive-data finding, retain private incident evidence and use the owner's authorized revoke/rotate process if a secret was exposed. History rewriting needs separate approval. For an editorial/build defect, correct the editable source and regenerate; preserve finalized historical reports and raw evidence.

Phase 5 checkpoint and recovery

Use the acceptance criteria: all mandatory tests/subchecks need evidence and PASS for engineering completion; unresolved critical safety issues block acceptance. Owner UAT stays a separate explicit decision. Recover publication errors through reviewed corrections/reverts preserving immutable records; do not rewrite history or expand lab scope to close a report.

Required lab deliverables

These five files are **available as blank templates** in the deliverable library. Work privately, record actual results only after execution and publish only reviewed summaries. The number shorthand used throughout this manual refers to this table.

Filename	Owning record
01-Lab-Environment-and-Architecture.xlsx	Hardware, four VMs, three zones, flows and capacity
02-Identity-and-Zero-Trust-Implementation.docx	Identity, endpoints, HTTPS, app roles and remote configuration
03-Security-Monitoring-and-Testing.xlsx	Events, tests, evidence, automation, recovery and owner acceptance
04-Troubleshooting-and-Lessons.xlsx	Real issues, corrections, retests and lessons
05-Final-Project-Submission.docx	Results summary, rubric, limitations and supporting records

Historical requirement and test transition

The historical mapping appendix preserves the earlier requirement/test labels for readers following old records. It is outside the practical lab instructions and adds no current task or test. Use the current coverage index for the ten FWR/FWT mappings.